

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block - B, I.P. Estate, New Delhi - 110 002

Date: 12-12-2025

NOTICE INVITING QUOTATION

Percentage rate of quotations are invited for the work: - **Major Repairs work of RCC Slab Plaster in room no. MS40, MF02, GS04, GS18 & Painting work in 28 nos. Rooms at Maharani Bagh Boys Hostel Room and Toilets SPA-D.**

Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work & in Annexure format.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.


The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on **18-12-25** before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,


Yours faithfully,
SD/-
Junior Engineer ©

Consultant engineer ©

*For Publishing on
SPA website*

*HW
16/12/2025*

Encl.: Schedule of work

Head CASS *Karan*

17 Engineer

Name of work - Major Repairs work of RCC Slab ceiling plaster in room
no No.MS40,MF02,GS04,GS18 & Painting work in 28 no. rooms at Maharani Bagh Boys
hostel Room and toilets SPA-D.

| | | | UNIT | QUANTL | RATE | AMOUNT |
|-------|---|--|------|--------|--------|------------|
| | | Repairs to underside of RCC slab of thickness 25mm to 50 mm (as per site condition) in patches of area 1 Sq. Meter and under including providing, mixing, placing, compacting, curing and straightening to surfaces wherever required, polymer modified galvanized steel reinforced cement concrete of (1:1.5:3) (cement:1.5 coarse sand:3 marble chips aggregate) of approved make (Fosroc/Pidilite/MC Bauchemie) to required levels and shapes at all heights and depths using 12 mm max to 7 mm size well graded marble chips aggregates including providing & placing unwrought shuttering/centering/scaffolding to required levels, shapes at all heights & depths, and providing, straightening, cutting & placing of galvanized steel reinforcement, with steel wire of 2-3 mm (dia.) and centre to centre distance between wires is 50 mm in RCC works (including binding wires) including providing and fixing of construction safety net below the repair surfaces as per approved sample and confirming IS:11057 (1984/2019) etc.(Including Painting) Item includes all necessary materials/fixing etc. complete as per approval and instructions of the Engineer/Project Manager. | SQM | 62 | 3636.5 | 225463 |
| 13.91 | 2 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | SQM | 740 | 25.15 | 18611 |
| 79.41 | 3 | Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification. Two or more coats on new work | SQM | 740 | 185.65 | 137381 |
| 13.8 | 4 | 13.80 Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth | SQM | 740 | 156.05 | 115477 |
| | | TOTAL AMOUNT | | | | 496932.00 |
| | | Terms& Conditions | | | | |
| 1 | | The work shall be completed with in 30 Days froms the date of issue of work order otherwise 1% penalty per day up to a maximum of 10% shall be imposed on gross amount of bill | | | | |
| 2 | | 2 % income tax will be deducted from the bill. | | | | |
| 3 | | The work shall be carried out as per C.P.W.D. specification and entire satisfaction of engineer-in-charge. | | | | |
| 4 | | 1% Water Charges will be deducted from the bill | | | | |
| 5 | | 1% Labour Cess will be deducted from the bill | | | | |
| | | | | | | AE (Civil) |