## SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI

4, Block - B, I.P. Estate, New Delhi - 110 002

Date: 12-12-2025

## NOTICE INVITING QUOTATION

Percentage rate of quotations are invited for the work; - Minor Repairs work of RCC Slab celling plaster & Painting work at Maharani Bagh Boys hostel Room and toilets No.MS68,MS67,MS66,MS61,MS59,MS09,MS07,MS06,MS03,MF03,MF07,MF65,73,MF27,GS05,GS11,GS12,G S15,GS17,GS01,ST06,ST07,ST08 SPA-D

. Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work & inAnnexure format.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 18-12-25before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Junior Engineer ©

Consultant engineer © Thyrox

Encl.: Schedule of work Head Chis Kovan.

17 Engineer

## Name of work :- Minor Repairs work of RCC Slab celling plaster & Painting work at Maharani Bagh Boys hostel Room and toilets

No.MS68,MS67,MS66,MS61,MS59,MS09,MS07,MS06,MS03,MF03,MF07,MF65,73,MF27,GS0 5,GS11,GS12,GS15,GS17,GS01,ST06,ST07,ST08 SPA-D.

	7	11,G512,G513,G517,G501,5100,5107,5100	UNIT	QUANTI.	RATE	AMOUNT
MR	1	Repairs to underside of RCC slab of thickness 25mm to 50 mm (as per site condition) in patches of area 1 Sq. Meter and under including providing, mixing, placing, compacting, curing and roughening to surfaces wherever required, polymer modified galvanized steel reinforced cement concrete of (1:1.5:3) (1cement:1.5 coarse sand:3 marble chips aggregate) of approved make (Fosroc/Pidilite/MC Bauchmie) to required levels and shapes at all heights and depths using 12 mm max to 7 mm size well graded marble chips aggregates including providing & placing unwrought shuttering/centering/scaffolding to required levels, shapes at all heights & depths, and providing, straightening, cutting & placing of galvanized steel reinforcment, with steel wire of 2-3 mm (dia.) and centre to centre distance between wires is 50 mm in RCC works (including binding wires) including providing and fixing of construction safety net below the repair surfaces as per approved sample and confirming IS:11057 (1984/2019) etc.(Including Painting) Item includes all necessary materials/fixing etc. complete as per approval and instructions of the Engineer/Project Manager.	SQM	130	3636.5	472745
13.91	2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	SQM	70	25.13	1700.5
<b>'</b> 0	3	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.	SQM	70	185.65	12995.5
13.8	4	Two or more coats on new work  13.80 Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth	SQM	70	156.05	10923.5
	-	TOTAL AMOUNT				498424.50
		Terms& Conditions	- 6	ander other	vice 1% per	alty per day i
	1	Terms& Conditions  The work shall be completed with in 30 Days froms the date of issue of work order otherwise 1% penalty per day up to a maximum of 10% shall be imposed on gross amount of bill.  2 % income tax will be deducted from the bill.				
	3	The work shall be carried out as per C.P.W.D. specification and entire satisfaction of engineer in charge.				
	4	1% Water Charges will be deducted from the bill.				
	5	1% Labour Cess will be deducted from the bill.				