

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI

4, Block B, I.P. Estate, New Delhi 110 002

Date: 01/07/26

NOTICE INVITING QUOTATION

Percentage rate of **quotations** are invited for the work:- **Repairing Painting Exterior and interior area including Lobby of auditorium Architecture Block SPA-D.**

~~Therefore~~, you are hereby requested to quote your rate for the above cited work in the attached schedule of work & in Annexure format.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.


The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 03/07/26 before 1:00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Yours faithfully


SD/-
11/7/26
Junior Engineer

~~Consultant engineer~~


11/7/2026

Head CA/Sec

Encl.. Schedule of work

Karan

For Publication The quotation on web - Portal -

Estimate

Subject : Repairing Painting Exterior and interior area including Lobby of auditorium Architecture Block SPA-D.

Head DSR	S.No.	Description of Items	Qty	Unit	Rate	Amount
13.8	1	Providing and applying 1 mm putty on wall to give smooth and even shade as per direction of the Engineer in charge .	900	sqm	156.05	140445.0
14.1.2	2	Repairs to plaster in patches of thickness 12 to 20 mm with 1 : 4 Cement mortar as per direction of the Engineer in charge .	50	sqm	560.5	28025.0
13.91	3	Removing dry or oil bound distemper / scrapping	900	sqm	25.15	22635.0
13.46.1	4	Painting with acrylic smooth exterior paint on walls	600	sqm	160.6	96360.0
15.56	5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	50	sqm	54.65	2732.5
13.91	6	Distemping with 1st quality acrylic distemper as per direction of the Engineer in charge . Two or more coats	400	sqm	111.65	44660.0
					Total Rs.	334858

[Handwritten Signature]