

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI

4, Block B, I.P. Estate, New Delhi 110 002

Date:12/10/26

NOTICE INVITING QUOTATION

Percentage rate of **quotations** are invited for the work:- **Renovation of P.M.W Store Room at Planning Campus SPA-D.**

Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 16/10/26 before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Yours faithfully


13/10/26
Junior Engineer

Consultant engineer


13/10/2026

Encl.. Schedule of work

Head CASE — for publish on SPA website.
Karan

Estimate

Subject : Renovation of PMW Store in Planning Building of SPA - Delhi .

DSR . Head	S.No.	Description of Items	Qty	Unit	Rate	Amount
15.56	1	Dismantling old plaster or skirting raking out joints and cleaning the surface .	94.6	Sqm	54.65	5169.89
15.2.1	2	Demolishing cement concrete manually / by mechanical means 1:3:6 as per direction of the Engineer in charge .	5.2	Cum	2434.25	12658.1
2.38	3	Filling available excavated earth in trenches , plinth , sides of foundation etc in layers	14.3	Cum	308.2	4407.26
15.7.4	4	Demolishing brick work manually / by meachanical means as per direction of the Engineer in charge .	1.8	Cum	2060.2	3708.36
4.1.3	5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering .	4.18	Cum	7878.5	32932.13
11.26	6	kota stone slab flooring over 20 mm thick base 11.26.1 25 mm thick	28	Sqm	1948.25	54551.00
11.27	7	Kota stone slab s 20mm thick in risers of steps , skirting , dado and pillars laid thick cement mortar 1:3 , including rubbing and polishing complete .	4	Sqm	2354.7	9418.80
6.4.1	8	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS : 2222 in superstructure	1.8	Cum	9344.35	16819.83
13.7	9	12 mm Cement Plaster finished with a floating coat of neat cement mix. 1 : 4	82	Sqm	425.55	34895.1
13.91	10	Removing dry or oil bound distemper , water proofing cement paint and the like by scrapping etc complete .	90	Sqm	25.15	2263.5
13.8	11	Providing and applying white cement based putty of average thickness of 1 mm of approved brand and manufacture .	90	Sqm	156.05	14044.5
13.41	12	Distempering with 1st quality acrylic distemper having VOC to achieve even shade and colour .	90	Sqm	185.65	16708.5
8.31	13	Providing and fixing 1st quality ceramic glazed wall tiles as per direction of the Engineer in charge .	48.5	sqm	1267.95	61495.58

14.1.2	14	Repairs to plaster in patches 12 mm to 20 mm in patches of area 2.5 sqm and under etc complete as per direction of the Engineer in charge.	18	Sqm	560.5	10089.00
M.R	15	Disposal of building rubbish / malba / similar unserviceable means etc including all lifts involved .	6	Cum	650	3900
13.99	16	Artificial enamel paint . Two or more coats as per direction of the Engineer in charge	100	Sqm	102.8	10280.00
13.46.1	17	Finishing walls with Acrylic smooth exterior paint of required shade . New work	82	Sqm	160.6	13169.2
10.26	18	Steel work welded in built up sections as per direction of the Engineer in charge .	182	kg	196.8	35817.6
12.8	19	Providing reinforced by organic fibres and inorganic synthetic fibres cement 6 mm thick corrugated sheets	20	Sqm	536.4	10728.0
					Total Rs.	353056.35

Deputy