

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block B, I.P. Estate, New Delhi 110 002

Date: 28/10/26

NOTICE INVITING QUOTATION

Percentage rate of **quotations** are invited for the work:- *Development of a new Conference - meeting room and workspace for the Construction Department on the 3rd floor planning building 4A-2.*

Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 30/10/26 before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Yours faithfully

[Signature]
28/10/26
Junior Engineer

Consultant engineer

[Signature]
28/10/2026

Encl.. Schedule of work

[Signature]
28/10/26

Name Of work :- Development of a Mini Conference-cum-Meeting Room and Workspace for the Conservation Department on the 3rd Floor Planning Block SPA-D

			UNIT	QUANTI.	RATE	AMOUNT
9.112	1	Providing and fixing 2nd class teak wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge. metre	Meter	100	102.15	10215
9.60.3	2	Providing ms hinges ISI marked IS: 3818 finished with nickel chromium plating grade I as per IS: 1068 and fixing with necessary screws etc., complete.	mtr.	20	261.15	5223
9.79.2	3	Providing and fixing special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete.	each	10	356.75	3567.5
9.80.	4	9.80 Providing and fixing 50 mm bright finished brass cup board or wardrob eknob of approved quality with necessary screws.	each	10	74.25	742.5
9.92.2	5	Providing and fixing chromium plated brass handles with necessary screws etc. complete:	each	25	206.25	5156.25
9.93	6	Providing and fixing chromium plated brass casement window fastener with necessary screws etc. complete.	each	20	155.45	3109
9.114.1	7	9.114 Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. Triple strip vertical type	each	10	52.2	522
13.69.1	8	Polishing on wood work with ready mixed wax polish of approved brand and manufacture : New work	Sqm	10	897.3	8973
9.97.2	9	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :	each	10	115.15	1151.5
9.18.1	10	9.18 Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 18 mm thick sqm	Sqm	45	1245.75	56058.75
9.127.2	11	9.127 Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.	Sqm	90	897.3	80757
9.126.1	12	Providing and fixing 12 mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick.	Sqm	2	2486.25	4972.5
9.115	13	Providing and fixing powder coated telescopic drawer channels 300 mm long with necessary screws etc. complete as per directions of Engineer-in-charge.	each	24	414.2	9940.8
9.9.1.1	14	9.9 Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, (weight not less than 10 kg per sqm) fixing with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class teak wood 35 mm thick	Sqm	2	4940.2	9880.4
Market rate	15	Providing and fixing of cloth pf approved colour etc as per direction of the Engineer in charge .	Sqm	10	388	3880

Parul

Market rate	16	Providing and fixing of roller blind with necessary arrangement for fixing of blind complete (including Control unit, Idler, Head rail, Bottom rail, operating chain, Fixing brackets & clamps, roller tube etc as per site requirement and direction of engineer-in-charge.) and fabric with the following specifications: 1) Composition: 3 Ply PVC+1 Ply Fiber Glass Black out 2) Coating: 1 Ply Fiber Glass Blackout 3) Weight: 520Gsm 4) Fabric Width: as per window width 5) Tearing Strength: 64 N Warp, 57 N Weft 6) Thickness:0.36 mm 7) Environmental Certificate: Green Guard	Sqm	5	3637	18185
13.91	17	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	50	25.15	1257.5
13.8	18	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	50	156.05	7802.5
13.41.1	19	13.41 Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	Sqm	50	185.65	9282.5
1745	20	Supply & Fixing of Square type 2'x2' LED Panel Light 36W, Recess Mount Type Natural White Color or Cool Day White ,Square Shape, Lumen output 3600 Lm, Body material Steel Sheet plus PC diffuser, Cutout Size 24x24 inch, 2x2 Grid Panel Backlight, Lumen, High Uniformity & CRI>80, Efficiency 100 lm/W, Compact integral design ,Multiple Lumen Packs & CCT Suiting Different Applications and Heights Super Slim With Just 35mm Depth Inside Ceiling 25000 hrs Ambient Temperature 45°C Surge 2.5 KV Internal, Operating Voltage 160-270V, THD <30% Uv Stabilised frame with uniformly diffused light due to high quality PC diffuser easily serviceable ballast Warranty for free replacement (1Years) Recess Mount type : Make: crompton, Havells, Philips	each	3	5252	15756
Market rate	21	Providing and carrying out electrical wiring/pointing work, including supply and installation of required wires, PVC casing-capping/channel, sockets, switch plates, switches, switch boxes/boards, and all necessary accessories, complete in all respects, as per site requirements and directions of the Engineer-in-Charge. All materials, labour, fixing, testing and commissioning shall be included in the item rate.	each	1	22500	22500
Market rate	22	Providing and laying 12 mm thick AC-5, grade laminate wooden flooring & skirting of Vista/Virgin or equivalent make and made having 0.2 mm thick direct laminate on top of specially developed substrate core (high density fibre board) of plank size as per manufacturer's specification having smart lock, joint tongue and groove construction including top of skirting should be sealed with 4mm thick teak wood lipping. The under layer has to be a 0.2 mm thick alkali resistant polyethylene sheet of density 30-32 kg. per cum on top to secure the floor. The work shall be carried out as per manufacturer's installation procedure and as per direction of Engineer-in-charge.	Sqm	25	1699.7	42492.5
Market rate	23	Providing PVC WALL PANELLING of thickness 5mm (±0.25) consisting of panels of desired size stuck on inner frame work of 50mm wide strips of 5mm (±0.25) thick Prelam PVC sheet. The panel & strips shall be Density of 600 Kg /Cbm Manufactured by an ISO-9001-2015 certified Company. The strips should have in their center a groove of 6mm width and 1mm depth for sinking the head of the screw used to fix the strips to the wall vertically at an equal interval of 10" between two PVC strips. The PVC strips shall be fixed to the wall using 65mm long M.S. screws through the groove in the strip by using PVC fasteners. The distance between two screws shall not be more than 200mm. A groove of 2mm may be left at the joint of two panels for aesthetic looks. The exact size of the panel and correspondingly of the grid may vary depending on the size of the wall. Optionally a strips of 5mm (±0.25) thick PVC sheet of width 75mm feathered at the edges shall be stuck at the places where two panels are	Sqm	20	2699	53980
						375405.20
		Terms & Conditions				
	1	The work shall be completed with in 15 Days froms the date of issue of work order otherwise 1% penalty per day up to a maximum of 10% shall be imposed on gross amount of bill				
	2	2 %income tax will be deducted from the bill				
					AE (Civil)	