SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block B, I.P. Estate, New Delhi 110 002

Date:25/11/26

NOTICE INVITING QUOTATION

Percentage rate of **quotations** are invited for the work:- **Miscellaneous Renovation and Improvement Works in the Office of Dean (Academics), including Wall Painting, Panelling, Concealment of Exposed Electrical Wiring and Provision of Pin-up Boards " in Planning Block SPA-D.**

Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 27/11/26before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Yours faithfully

25/11/2026

Junior Engineer

AE/C/F/1125
25/11/26

Consultant ~~engineer~~

25/11/2026

Head CASS

Enci.. Schedule of work

Name Of work :- Miscellaneous Renovation and Improvement Works in the Office of Dean (Academics), including Wall Painting, Panelling, Concealment of Exposed Electrical Wiring and Provision of Pin-up Boards " in Planning Block SPA-D.

			UNIT	QUANTI.	RATE	AMOUNT
M/R	1	Providing and fixing of cloth pf approved colour etc as per direcction of the Engineer in charge .	Sqm	20	388	7760
9.112	2	Providing and fixing 2nd class teak wood lipping/ moulded beading or taj beading of size 18X5 mm fixed with wooden adhesive of approved quality and screws/nails on the edges of the Pre-laminated particle board as per direction of Engineer-in-charge. metre	Meter	16	102.15	1634.4
13.69.1	3	Polishing on wood work with ready mixed wax polish of approved brand and manufacture : New work	Sqm	10	897.3	8973
M/R	4	Providing and fixing flat pressed commercial ply board of approved brand and manufacturer in wooden cabinet ,cupboard, counter,etc complete as per direction of engineer-incharge.6 mm	Sqm	22	1584.5	34859
13.91	5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	50	25.15	1257.5
13.8	6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	50	156.05	7802.5
13.41.1	7	13.41 Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	Sqm	50	185.65	9282.5
M/R	8	Providing PVC WALL PANELLING of thickness 5mm (±0.25) consisting of panels of desired size stuck on inner frame work of 50mm wide strips of 5mm (±0.25) thick Prelam PVC sheet. The panel & strips shall be Density of 600 Kg /Cbm Manufactured by an ISO-9001-2015 certified Company. The strips should have in their center a grove of 6mm width and 1mm depth for sinking the head of the screw used to fix the strips to the wall vertically at an equal interval of 10" between two PVC strips. The PVC strips shall be fixed to the wall using 65mm long M.S. screws through the groove in the strip by using PVC fasteners. The distance between two screws shall not be more than 200mm. A groove of 2mm may be left at the joint of two panels for aesthetic looks. The exact size of the panel and correspondingly of the grid may vary depending on the size of the wall. Optionally a strips of 5mm (±0.25) thick PVC sheet of width 75mm feathered at the edges shall be stuck at the places where two panels are joined, using solvent cement.	Sqm	20	2699	53980
9.133.2.1	9	9.133.2 Multipurpose cement board reinforced with suitable fibre cement screw.8 mm thick cement fibre board as per IS : 14862	Sqm	10	1443.45	14434.5
M/R	10	Providing & Fixing of soft boards on the walls including dismantling the old of cellotex make complete as per direction of engineer-in-charge.	Sqm	20	1653	33060
						173043.40
		Terms& Conditions				
	1	The work shall be completed with in 5 Days froms the date of issue of work order otherwise 1% penalty per day up to a maximum of 10% shall be imposed on gross amount of bill.				
	2	2 %income tax will be deducted from the bill.				
	3	The work shall be carried out as per C.P.W.D. specification and entire satisfaction of engineer-in-charge.				
					AE (Civil)	